

Molecular gas as the driver of fundamental galactic relations

Journal Article**Author(s):**

Bothwell, M. S.; Maiolino, R.; Peng, Y.; Ciccone, Claudia; Griffith, H.; Wagg, J.

Publication date:

2016

Permanent link:

<https://doi.org/10.3929/ethz-b-000112816>

Rights / license:

[In Copyright - Non-Commercial Use Permitted](#)

Originally published in:

Monthly Notices of the Royal Astronomical Society 455(2), <https://doi.org/10.1093/mnras/stv2121>

Molecular gas as the driver of fundamental galactic relations

M. S. Bothwell,^{1,2★} R. Maiolino,^{1,2} Y. Peng,^{1,2} C. Cicone,³ H. Griffith^{1,2} and J. Wagg⁴

¹*Cavendish Laboratory, University of Cambridge, 19 J.J. Thomson Avenue, Cambridge CB3 0HE, UK*

²*Kavli Institute for Cosmology, University of Cambridge, Madingley Road, Cambridge CB3 0HA, UK*

³*ETH Zurich, Institute for Astronomy, Wolfgang-Pauli-Strasse 27, CH-8093 Zurich, Switzerland*

⁴*SKA Organization, Lower Withington Macclesfield, Cheshire SK11 9DL, UK*

Accepted 2015 September 10. Received 2015 September 10; in original form 2015 July 3

ABSTRACT

There has been much recent work dedicated to exploring secondary correlations in the mass–metallicity relation, with significant dependence on both the SFR (SFR) and H I content being demonstrated. Previously, a paucity of molecular gas data (combined with sample selection bias) hampered the investigation of any such relation with molecular gas content. In this work, we assemble a sample of 221 galaxies from a variety of surveys in the redshift range $0 < z < 2$, to explore the connection between molecular gas content and metallicity. We explore the effect of gas mass on the mass–metallicity relation, finding that the offset from the relation is negatively correlated against both molecular and total gas mass. We then employ a principle component analysis technique to explore secondary dependences in the mass–metallicity relation, finding that the secondary dependence with gas mass is significantly stronger than with SFR, and as such the underlying ‘fundamental metallicity relation’ is between stellar mass, metallicity, and gas mass. In particular, the metallicity dependence on SFR is simply a byproduct of the dependence on the molecular gas content, via the Schmidt–Kennicutt relation. Finally, we note that our principle component analysis finds essentially no connection between gas-phase metallicity and the *efficiency* of star formation.

Key words: galaxies: abundances – galaxies: evolution – galaxies: formation – galaxies: statistics.

1 INTRODUCTION

Much of the quest to understand the processes driving galaxy evolution has concentrated on understanding the so-called scaling relations, distinctive correlations existing between large-scale physical parameters of galaxies. These scaling relations allow insight into the mechanisms underlying galaxy formation by providing simple, quantitative tests for models – both analytical and numerical – to match. Indeed, the ability (or otherwise) of a model to reproduce a variety of observed scaling relations has become a critical metric by which a model’s success is judged.

In recent years, the well-known scaling relations between stellar mass and metallicity (the ‘mass–metallicity relation’), and stellar mass and star formation rate (SFR; the ‘main sequence’ of galaxy evolution) have been extended into a three-dimensional relation, known as the fundamental metallicity relation (FMR; Lara-López et al. 2010; Mannucci et al. 2010. Galaxies up to at least $z \sim 2.5$ lie on the surface defined by the FMR, on which (a) more massive galaxies have higher metallicities, and (b) at a given stellar mass, galaxies with higher SFRs have systematically lower metallicities.

The existence of the FMR has provided an excellent target for models to reproduce, with a variety of models successfully reproducing the general form of the relation, including analytical models (Davé, Finlator & Oppenheimer 2012; Dayal, Ferrara & Dunlop 2013), semi-analytical models (Yates & Kauffmann 2014), and SPH/radiative transfer models (Obreja et al. 2014). As noted by Bothwell et al. (2013b), these models have primarily explained the correlation between stellar mass, metallicity, and SFR in terms of the global behaviour of gas, which can dilute the metallicity of the Interstellar Medium (ISM) via pristine inflows, trigger metallicity-enriching bursts of star formation, and remove metals from the ISM in the form of galactic winds.

Based on this, Bothwell et al. (2013b) conducted a study of 4253 local galaxies, finding that the mass–metallicity relation also exhibited a significant secondary dependence on mass of atomic hydrogen (H I), to the extent that the ‘H I–FMR’ was potentially more fundamental than the correlation with SFR (in terms of the scatter around the respective relations). As with the SFR–FMR before, this has proved a fertile area for models, with several authors concluding that it is indeed the gas content of galaxies that fundamentally underlies and drives the mass–metallicity relation. Davé et al. (2012) present an analytical model of galaxy evolution, which predicts that metallicity will anti-correlate with H I mass. Zahid et al. (2014) present a model whereby the metallicity of galaxies is regulated by

*E-mail: matthew.bothwell@gmail.com

the gas-to-stellar mass ratio, such that the mass–metallicity relation can be seen as a consequence of the underlying metallicity/gas-to-stellar mass ratio scaling. Ascasibar et al. (2015) conduct a similar investigation, extending to resolved studies of local galaxies, and reaching similar conclusions. (See also Magrini et al. 2012; Lara-López & Hopkins 2014; Ho et al. 2015) for additional work.)

One potential surprise, however, was the lack of a clear dependence with *molecular* gas. While Bothwell et al. (2013b) found a close and tight relationship between stellar mass, metallicity, and H I mass, any such relation with H₂ mass remained elusive. As discussed by Bothwell et al. (2013b), this was potentially due to two factors: (1) sample selection bias, resulting in a small number of galaxies covering insufficient parameter space, and (2) the fact that measuring H₂ mass requires a ‘conversion factor’ (to convert from its observable tracer, ¹²CO), which is itself a function of metallicity. This lack of connection between molecular gas mass and the mass–metallicity relation was particularly surprising, because the physical processes thought to be driving the H I-FMR (including star formation-triggering inflows, and metal-rich outflows) are intimately connected with the molecular gas component of the ISM. Furthermore, it has long been established that molecular gas and star formation are tightly correlated across a wide range of galaxy types, via the Kennicutt–Schmidt relation (Schmidt 1959; Kennicutt 1998); given this relation, an H₂-FMR should be expected on the basis of the existence of the SFR–FMR alone. As such, Bothwell et al. (2013b) concluded that while an H₂-FMR was likely to exist, quantifying its existence was beyond the scope of their data.

In this work, we assemble a large sample of galaxies, from dwarf galaxies in the local Universe to extreme starbursts at $z \sim 2$, to explore the connection between the molecular gas content of galaxies, and their gas-phase metallicity. First, we examine the effect of molecular gas mass on metallicity scaling relations, by searching for an ‘H₂-FMR’ effect, whereby galaxies show offsets from the mass–metallicity relation which correlate with molecular (and total) gas mass. We then adopt a non-parametric statistical approach, and use a principle component analysis (PCA) technique to examine correlations in stellar mass/metallicity/gas mass parameter space, demonstrating that (a) the most significant ‘secondary correlation’ in the mass–metallicity relation is indeed with gas content, and (b) there is very little correlation between metallicity and star formation efficiency (SFE).

Throughout this work, we use a Kroupa (2001) IMF, and a cosmology following the latest Planck results, with $H_0 = (67.8 \pm 0.9)$ km s⁻¹ Mpc⁻¹ and $\Omega_m = 0.308 \pm 0.012$ (Planck Collaboration XIII 2015).

2 SAMPLE SELECTION

In this work, we will be characterizing the scaling relations between a variety of parameters: stellar mass, metallicity, SFR, and gas content (both atomic and molecular). We have selected our samples based on the simultaneous availability of all of these parameters. Stellar masses, SFRs, atomic gas masses, and metallicities (typically measured via optical strong line diagnostics) are comparably easily measured, and are widely available in the literature. Molecular gas masses (measured using observations of ¹²CO) are less widely available, and it is the availability of this latter parameter that typically represents the limiting factor in our sample selection.

In the local Universe, we use three recent surveys for molecular gas which fulfil these criteria excellently: COLD GASS (Saintonge et al. 2011a), the *Herschel* Reference Survey (HRS; Boselli, Cortese & Boquien 2014), and ALLSMOG (Bothwell et al.




Figure 1. Histogram of the stellar masses of galaxies in the samples used in this work. Only galaxies that obey the selection criteria detailed in Section 2 are shown. The main panel shows the combined stellar mass histogram, while the smaller inset panels show histograms of the stellar mass for each separate sample.

2014). Both COLD GASS and ALLSMOG are selected from the SDSS spectroscopic survey, and as such have available optical spectra for deriving metallicities. Optical spectroscopy for the HRS is available from Boselli et al. (2013). In order to gather better statistics at the low-mass, low-metallicity end of the distribution, we also use galaxies from the volume-limited Local Volume Legacy (LVL) survey, which (being a complete volume-limited sample within 11 Mpc) contains galaxies of lower mass than appear in other samples.

We also wish to extend our study beyond the local Universe: in order to compare the samples discussed above to those at higher redshifts, we gather samples of both ‘normal’ star-forming galaxies (selected using optical colour cuts, and lying on or around the main sequence) and luminous sub-millimetre galaxies, SMGs (selected via their sub-mm flux, and having extreme SFRs significantly above the star-forming ‘main sequence’). These high- z galaxies typically lie around $z \sim 2$.

Below, we briefly describe these various samples. A histogram of stellar masses for galaxies used in this work (separated by sample) is shown in Fig. 1. Histograms of other physical parameters are shown in Fig. 2. Our combined samples provide a mass coverage of approximately three orders of magnitude, from $8.5 < \log M_*/M_\odot < 11.5$. In total, our combined sample consists of 221 galaxies from $0 < z \lesssim 2$.

2.1 Local universe surveys

2.1.1 ALLSMOG

ALLSMOG, the Apex Low-redshift Legacy Survey for MOlecular Gas, is the Atacama Pathfinder Experiment telescope (APEX) large




Figure 2. Histogram of the SFRs (left-hand panel), molecular gas masses (central panel), and metallicities (right-hand panel) of galaxies in the samples used in this work. As before, only galaxies that obey the selection criteria detailed in Section 2 are shown.

programme designed to survey molecular gas in local galaxies with stellar masses $8.5 < \log(M_*/M_\odot) < 10.0$. The survey covers the local Universe, $0.010 < z < 0.025$ ($= 40 \lesssim D/\text{Mpc} \lesssim 110$), excluding the very nearby Universe to ensure that the 27 arcsec APEX beam recovers the total CO flux.

Upon completion, the ALLSMOG survey will have CO measurements (both detections and upper limits) for ~ 100 low mass ($< 10^{10} M_\odot$) galaxies. In this work, we use the ‘halfway’ data release presented by Bothwell et al. (2014) which consists of 42 galaxies. Data observations and reduction were undertaken as described in that work. Being drawn from the SDSS spectroscopic survey, all ALLSMOG galaxies have available optical spectra. One of the aims motivating the ALLSMOG survey was to study the connection between metallicity and molecular gas content, and so all ALLSMOG galaxies have the complete suite of optical line fluxes necessary for deriving metallicities (see Section 2.3.1 for an explanation of the metallicity derivation). All ALLSMOG galaxies are selected from the SDSS spectroscopic survey, and have their stellar masses and SFRs readily available. Both stellar masses and SFRs, corrected for aperture effects caused by the fibre, are provided by the MPA-JHU group.¹ SFRs are derived using optical line fitting, as described in Brinchmann et al. (2004). Stellar masses are likewise measured using the fitting technique described by Kauffmann et al. (2003a). Uncertainties on these parameters are typical for SDSS galaxies – approximately ~ 0.3 and ~ 0.15 dex for SFRs and stellar masses, respectively.

The ALLSMOG galaxies used in this analysis have a metallicity range $[8.52 < 12 + \log(\text{O}/\text{H}) < 9.17]$, an SFR range $[0.04 < \text{SFR}/M_\odot \text{ yr}^{-1} < 12.0]$, and lie between stellar masses $[8.5 < \log M_*/M_\odot < 10.0]$.

All ALLSMOG galaxies published in the first data release are used in this analysis: a total of 42 galaxies.

2.1.2 COLD GASS

The COLD GASS survey is a large Institut de Radioastronomie Millimétrique (IRAM) programme, designed to survey molecular gas in massive $z \sim 0$ galaxies, with $\log(M_*/M_\odot) > 10$. The survey covers the redshift range $0.025 < z < 0.05$ ($= 110 \lesssim D/\text{Mpc} \lesssim 220$), and is selected at random from the parent GASS sample (Catinella et al. 2010). The COLD GASS sample is discussed in detail by Saintonge et al. (2011a).

As with the ALLSMOG sample, COLD GASS is drawn from the SDSS spectroscopic survey and has associated available spectra, which supply both stellar masses and SFRs (as detailed in the ALLSMOG description above). We remove AGN (which contaminate the optical line fluxes, making the resultant metallicity estimates inaccurate) from the COLD GASS sample using the BPT (Baldwin, Phillips & Telervich 1981) cut given by Kauffmann et al. (2003b). The COLD GASS galaxies used here have a metallicity range $[8.87 < 12 + \log(\text{O}/\text{H}) < 9.29]$, an SFR range $[0.04 < \text{SFR}/M_\odot \text{ yr}^{-1} < 27]$, and lie between stellar masses $[10.0 < \log M_*/M_\odot < 11.5]$.

After discarding AGN, and galaxies with discrepancies between their R23 and $[\text{N II}]/\text{H}\alpha$ metallicities (see Section 2.3.1 below), we are left with 115 COLD GASS galaxies.

2.1.3 Herschel Reference Survey

The HRS is a *Herschel*-guaranteed time key project, designed to study a complete, volume limited sample of galaxies at distances $15 < D/\text{Mpc} < 25$. Within these limits the survey is highly complete. A full survey description is given by Boselli et al. (2010).

Lying closer than 25 Mpc, the HRS galaxies are too nearby to be effectively probed by a fibre survey such as SDSS (the 3 arcsec SDSS fibre would cover only a tiny fraction of the galaxy disc). However, ancillary parameters – including both stellar masses and optical spectra – are available from other sources. Stellar masses for the HRS are presented by Cortese et al. (2012), and were derived using *i*-band luminosities, with a typical uncertainty of ~ 0.15 dex. SFRs for the HRS galaxies can be calculated from a combination of UV and IR fluxes (UV fluxes presented by Cortese et al. (2012) and IR fluxes, presented by Bendo, Galliano & Madden 2012). Briefly, we define the FUV attenuation via the IRX’ parameter, $\text{IRX} = \log(L_{\text{IR}}/L_{\text{FUV, obs}})$:

$$A(\text{FUV}) = -0.028X^3 + 0.392X^2 + 1.094X + 0.546, \quad (1)$$

where X is ‘IRX’ (Burgarella, Buat & Iglesias-Páramo 2005). SFRs are then calculated from the attenuation-corrected FUV luminosity:

$$\log \text{SFR} = \log L_{\text{FUV, corr}} - 9.68, \quad (2)$$

which is an SFR prescription derived for use with the *GALEX* bands by Iglesias-Páramo et al. (2006). FUV, corr is the FUV luminosity, corrected for the effects of UV attenuation. We have reduced their original UV luminosity to SFR conversion factor by a factor of 1.5, in order to convert from their Salpeter (1955) IMF to the Kroupa (2001) IMF used to calculate SDSS parameters (see Salim et al. 2007 for details).

¹ <http://www.mpa-garching.mpg.de/SDSS/DR7/>

Optical spectra for the HRS, presented by Boselli et al. (2013), were taken by the 1.9-m telescope at Observatoire de Haute Provence, and cover the spectral range 3600–6900 Å, allowing metallicities to be derived identically as for the SDSS samples described above. Again, we use a BPT cut to remove AGN from the sample, and do not use galaxies with discrepant R23 and $[\text{N II}]/\text{H}\alpha$ metallicities (as described by Section 2.3.1 below). The HRS galaxies used here have a metallicity range $[8.57 < 12 + \log(\text{O}/\text{H}) < 9.05]$, an SFR range $[0.70 < \text{SFR}/M_{\odot} \text{ yr}^{-1} < 16.5]$, and lie between stellar masses $[8.9 < \log M_{*}/M_{\odot} < 10.4]$.

After these cuts, we are left with 24 HRS galaxies.

2.1.4 LVL survey

In addition to the three dedicated CO surveys discussed above, we also include galaxies from the volume-limited LVL survey. LVL is an Infrared Array Camera (IRAC) and Multiband Imaging Photometer for Spitzer (MIPS) Legacy survey of a volume-limited sample of 258 galaxies, designed to be statistically complete within 11 Mpc. The LVL survey was designed to work in synergy with ancillary data sets, including the UV and H α survey 11HUGS (11 Mpc H α and UV Galaxy Survey). The combined data set is volume limited out to 11 Mpc (excluding the ‘zone of avoidance, defined by the Galactic plane $|b| \lesssim 20^{\circ}$), with a magnitude limit $B < 15$.

Stellar masses for the LVL sample have been estimated by Bothwell, Kennicutt & Lee (2009), by combining photometry with a colour-dependent mass-to-light ratio, taken from the models of Bell & de Jong (2001). Bothwell et al. (2009) quote the estimated uncertainty on the stellar masses as ~ 0.3 dex. Gas data, both atomic and molecular, were compiled from a range of literature sources by Bothwell et al. (2009). SFRs for the LVL sample were derived by Lee et al. (2009), by combining UV and IR fluxes as per the method outlined above. The average uncertainty on these SFRs is approximately ~ 0.3 dex.

The final required data product, optical metallicity data, is compiled and presented by Marble et al. (2010). Requiring both molecular gas data and an optical metallicity measurement serves to eliminate much of the LVL sample: in total, 23 galaxies from LVL have the full complement of required data. (One of these galaxies, however – UGC05364 – has its metallicity estimated using observations of planetary nebulae – a unique method, not shared by any other galaxy used in this analysis. We therefore discard UGC05364 from the sample.) The LVL galaxies in our combined sample have a metallicity range $[8.01 < 12 + \log(\text{O}/\text{H}) < 9.31]$, an SFR range $[0.04 < \text{SFR}/M_{\odot} \text{ yr}^{-1} < 5.2]$, and lie between stellar masses $[8.4 < \log M_{*}/M_{\odot} < 11.5]$.

The LVL sample used in this analysis consists of 22 galaxies.

2.2 Galaxies at high redshift

2.2.1 Main-sequence star-forming galaxies

Our sample of high- z ‘main-sequence’ star-forming galaxies is taken from the PHIBBS survey for molecular gas in $1 < z < 3$ ‘main-sequence’ galaxies (Tacconi et al. 2013). These ‘main-sequence’ galaxies are selected via the ‘BX/BM’ optical colour-selection criteria (which approximately selects ‘normal’ star-forming galaxies at high- z ; details of this selection criteria are given in Steidel et al. 2004).

Galaxies in the PHIBBS survey lie at two distinct epochs: $z \sim 1.2$ and $z \sim 2.2$. The lower redshift galaxies are unsuitable for inclusion in this work, as their optical spectra (provided by the DEEP2 survey)

do not cover any suitable metallicity-tracing line ratios. The galaxies in the higher redshift bin, however, have been observed with VLT/SINFONI (Newman et al. 2012), and have publicly available near-IR spectroscopy covering the H α and [N II] lines, which we use to derive gas-phase metallicities (as described in Section 2.3.1 below).

Stellar masses, molecular gas data, and SFRs for these galaxies have been taken from Tacconi et al. (2013). To briefly summarize, stellar masses have been derived from UV-to-IR population synthesis modelling, and SFRs were calculated using a combination of UV, optical continuum, H α , and 24 μm continuum fluxes. Tacconi et al. (2013) quote a typical stellar mass uncertainty of 0.13 dex, and a typical SFR uncertainty of 0.15 dex. Molecular gas data for this sample were obtained using the IRAM Plateau de Bure Interferometer. Due to the redshift of the sample, the sources here are observed in the $^{12}\text{CO}(3-2)$ line – for the purposes of calculating gas masses, we have converted down to equivalent $^{12}\text{CO}(1-0)$ luminosities by assuming a ‘Milky Way’-like CO excitation, appropriate for these normal star-forming galaxies. The high- z ‘main-sequence’ galaxies in our sample have a metallicity range $[8.61 < 12 + \log(\text{O}/\text{H}) < 9.05]$, an SFR range $[30 < \text{SFR}/M_{\odot} \text{ yr}^{-1} < 245]$, and lie between stellar masses $[9.8 < \log M_{*}/M_{\odot} < 11.4]$.

Our final sample of high- z main-sequence galaxies consists of nine objects.

2.2.2 Sub-mm galaxies

We also include a sample of galaxies selected at sub-mm wavelengths (typically $S_{850} \gtrsim 5\text{mJy}$), known as sub-mm galaxies (SMGs). SMGs are high-redshift dusty galaxies with extreme SFRs ($\gtrsim 1000 M_{\odot} \text{ yr}^{-1}$). The source of the high SFRs exhibited by SMGs remains a matter of debate, but it is likely that the population contains both major mergers and extreme, ‘maximum starburst’ discs. Either way, it is clear that SMGs represent an extreme population lying far above the star-forming ‘main sequence’ at their redshifts. The inclusion of SMGs in our combined sample will extend the dynamic range of our analysis, in terms of both parameter space and the range of ISM environments sampled.

Our sample of SMGs lie at $z \sim 2$, and are taken from the sample presented by Chapman et al. (2005). Metallicities were derived from Keck/NIRSPEC near-IR spectroscopy (Swinbank et al. 2004), which covers both the H α and [N II] emission lines (again see Section 2.3.1 below for details of the metallicity derivation). We note that SMGs are highly dusty galaxies, and as such optical emission lines may not fully trace regions of active star formation. However in the absence of well-calibrated far-IR diagnostics (as described in e.g. Nagao et al 2011), these optical lines remain the only way to estimate metallicities in SMGs. We therefore proceed with the metallicity calibration, and simply warn readers that the metallicity values for our SMGs may be uncertain. Stellar masses for these SMGs were derived from full population synthesis modelling by Hainline et al. (2011), and SFRs were calculated using IR fluxes (derived from the far-IR-radio correlation) by Bothwell et al. (2013a). Uncertainties on SFRs and stellar masses for SMGs are typically of the order 0.3 dex (as given by Hainline et al. 2011 and Bothwell et al. 2013a).

Molecular gas masses were taken from the CO survey by Bothwell et al. (2013a). As with the high- z main-sequence galaxies above, molecular gas masses are based on mid- J ^{12}CO measurements – either $^{12}\text{CO}(4-3)$ or $^{12}\text{CO}(3-2)$. We have adjusted these down to the equivalent $^{12}\text{CO}(1-0)$ luminosities using the

SMG CO excitation derived by Bothwell et al. (2013a). One SMG (SMMJ030227.73+000653.3) has an unusually high $[\text{N II}]/\text{H}\alpha$ ratio; as noted by Swinbank et al. (2004), this is likely indicative of contamination by AGN activity. As such, we exclude it from our analysis.

The SMGs in our analysis have a metallicity range $[8.74 < 12 + \log(\text{O}/\text{H}) < 9.09]$, an SFR range $[390 < \text{SFR}/M_{\odot} \text{ yr}^{-1} < 2890]$, and lie between stellar masses $[10.3 < \log M_{*}/M_{\odot} < 11.2]$.

Excluding SMMJ030227.73+000653.3, our final SMG sample consists of nine galaxies.

2.3 Deriving physical parameters

2.3.1 Deriving metallicities

For all galaxies in this work (with the exception of some galaxies in the LVL sample: see below), we derive gas-phase metallicities using optical strong-line fluxes. Where possible, we take optical line fluxes from SDSS (this is applicable for the ALLSMOG and COLD GASS samples). Following Mannucci et al (2010), we selected galaxies for inclusion in our ALLSMOG sample by requiring a signal-to-noise ratio of 25 in the $\text{H}\alpha$ line – this ensures that the main optical lines are generally detected at high enough S/N to reliably derive a metallicity. All galaxies in the COLD GASS sample also fulfil this criteria. Mean line flux errors for our SDSS sources are as follows: $\text{H}\alpha_{\text{err}} \sim 4$ per cent; $[\text{N II}]_{\text{err}} \sim 5$ per cent; $\text{H}\beta_{\text{err}} \sim 25$ per cent; $[\text{O II}]3727_{\text{err}} \sim 48$ per cent; $[\text{O III}]5007_{\text{err}} \sim 28$ per cent; $[\text{O III}]4959_{\text{err}} \sim 31$ per cent. The faintest line detected is generally $[\text{O II}]3727$, and on average sources in our samples have $[\text{O II}]3727$ detected with an S/N ratio of ~ 2 . All lines are individually corrected for dust extinction, which is estimated using the $\text{H}\alpha/\text{H}\beta$ ratio, and a Milky Way extinction curve.

For ease of comparison, we follow Mannucci et al. (2010) in estimating metallicity based on two independent diagnostics: (1) the $[\text{N II}]/\text{H}\alpha$ ratio, and (2) the R23 parameter = $([\text{O II}]3727 + [\text{O III}]4958, 5007)/\text{H}\beta$. We then use the abundance calibrations of Maiolino et al. (2008) to calculate two separate metallicity measurements, one for each diagnostic. We take as our final metallicity value the mean of these two metallicity measurements, discarding any galaxies for which the methods give answers discrepant by >0.2 dex: such galaxies are likely to have inaccuracies in one or both metallicity diagnostics, and as such are unreliable. We note that nine galaxies in our ALLSMOG sample lie at $z < 0.019$, and thus the $[\text{O II}]3727$ line does not fall within the SDSS spectral range. For these nine galaxies, instead of the R23 parameter (which requires the detection of the $[\text{O II}]3727$ line) we adopt the metallicity as listed in the MPA-JHU catalogue (which is derived following Tremonti et al. 2004), adjusted for our metallicity calibration. We then, as above, take the mean of this value and the value derived using the $[\text{N II}]/\text{H}\alpha$ ratio.

One potential source of metallicity bias in our SDSS-observed samples is due to aperture effects. SDSS is a fibre-based spectroscopic survey, and the 3 arcsec fibre may only sample the central few kpc of some galaxies, if they are nearby, and subtend large areas on the sky. Given the existence of metallicity gradients, this may cause abundance estimates to be biased high (though this effect is likely to be small, as gradients in star-forming galaxies tend to be shallow – ~ 0.1 dex/ R_{e} ; Sánchez et al. 2014). Kewley, Jansen & Geller (2005) estimate that a ‘fibre covering fraction’ of 20 per cent is sufficient to recover the metallicity of a galaxy without aperture bias. If we remove the ALLSMOG and COLD GASS galaxies which fail this criteria (3 ALLSMOG galaxies, and 33 COLD GASS galaxies), our

results are unaffected. For the remainder of this work, we therefore proceed with the full samples as described above.

To recap the various sources of the non-SDSS spectroscopy, HRS galaxies have long-slit integrated spectroscopy presented by Boselli et al. (2013), high- z ‘main-sequence’ galaxies have near-IR spectra presented by Newman et al. (2012), and the SMGs have near-IR spectra presented by Swinbank et al. (2004). For the galaxies at high-redshift (both main sequence and SMGs), the full suite of optical strong lines is not available for each source. Instead, we estimate their metallicities based on the $[\text{N II}]/\text{H}\alpha$ ratio alone, again using the abundance calibrations provided by Maiolino et al. (2008).

As mentioned in Section 2.1.4 above, galaxies in the LVL sample have metallicities compiled from the literature by Marble et al. (2010). As noted by those authors, the metallicity data for many of these galaxies has been amassed over a number of years from a large number of disparate observations. As such it is challenging to put all the LVL metallicities into a common calibration framework. Indeed, Marble et al. (2010) do not attempt to do so, simply noting that the non-uniform calibrations add an additional uncertainty across the sample of ~ 0.2 dex. We follow this approach, and do not attempt to standardize the LVL metallicity measurements. Instead, we apply an additional 0.2 dex of uncertainty to all LVL metallicity measurements when fitting to the data. We stress that none of our conclusions are dependent on the inclusion of LVL – repeating our analysis without the LVL sample does not significantly change our results.

2.3.2 Deriving H_2 masses

Molecular hydrogen masses can be calculated from the CO luminosity, L'_{CO} , by assuming a CO/H_2 conversion factor α_{CO} :

$$M(\text{H}_2) = \alpha_{\text{CO}} L'_{\text{CO}(1-0)} \quad (3)$$

There has been a vast amount of work over the last few decades dedicated to empirically measuring, and theoretically modelling, α_{CO} (Bolatto, Wolfire & Leroy 2013 gives a recent review). While a number of physical factors can cause α_{CO} to vary, it is likely that the dominant factor is metallicity, with α_{CO} increasing rapidly as metallicity decreases. In this work, we will present results by adopting a CO/H_2 conversion factor that varies with metallicity. Several metallicity-dependent CO/H_2 conversion factor prescriptions are given in a recent review by Bolatto et al. (2013). In particular, we will explore results derived using four recent metallicity-dependent conversion factors, derived by Wolfire, Hollenbach & McKee (2010), Glover & Mac Low (2011), Narayanan et al. (2012), and Feldmann, Gnedin & Kravtsov (2012).

Uncertainties on molecular gas masses are dominated by systematic uncertainty concerning the CO/H_2 conversion factor. Uncertainties on CO fluxes, absolute flux calibration, and aperture corrections contribute, at most, ~ 20 per cent uncertainty to the final value of $M(\text{H}_2)$. The systematic uncertainty due to the CO/H_2 conversion factor is difficult to estimate (Saintonge et al. 2011a estimate a combined uncertainty, including systematic uncertainty on the conversion factor, of 0.3 dex). We have attempted to mitigate systematics due to the conversion factor by calculating our results for a range of metallicity-dependent factors. For the purposes of our analysis, however, we adopt a conservative total uncertainty of 0.3 dex on our molecular gas masses.




Figure 3. The mass–metallicity relation for the galaxies in our sample. The grey shaded areas are taken from Tremonti et al. (2004), and show the area that contains 64 per cent (light shaded area) and 90 per cent (dark shaded area) of all SDSS galaxies. We have adjusted the metallicity scaling for the Maiolino et al. (2008) calibration used in this work. We have calculated molecular gas masses using the (metallicity-dependent) CO/H₂ conversion factor from Wolfire et al. (2010). The dashed line is the mass–metallicity fit to the sample of galaxies used in this work. Galaxies at high-*z*, which have greater uncertainty on their metallicity estimates, are shown with error bars. Open symbols show galaxies not detected in ¹²CO, at the position of the 3 σ upper limits on their gas mass.

3 RESULTS: MOLECULAR GAS AND THE MASS–METALLICITY RELATION

We turn now to an examination of the effect of molecular gas on the scatter in the mass–metallicity relation. As discussed in the introduction, significant relationships have been discovered between the mass–metallicity relation and both SFR (the ‘FMR’; Mannucci et al. 2010; Lara-López et al. 2010) and H I (Bothwell et al. 2013b). Any relationship with molecular gas has thus far proved elusive, due to a likely combination of small available sample sizes, and potential degeneracy between metallicity and molecular gas masses (derived using a conversion factor which is itself strongly dependent on metallicity). The combined sample assembled in this work represents a uniquely ideal data set for examining any potential trends between metallicity and molecular gas mass, due to its dynamic range in both parameters.

Fig. 3 shows the mass–metallicity relation for galaxies in our combined sample. The original samples are differentiated with different symbols (shown in the inset key). The combined sample broadly follows the established *z* ~ 0 mass–metallicity relation (the dark and light shaded regions in the background show the 1 σ and 2 σ distributions in the mass–metallicity relation, as measured for SDSS galaxies by Tremonti et al. 2004, adjusted for the metallicity calibrations used in this work). As expected, higher-*z* galaxies generally fall below the *z* ~ 0 mass–metallicity relation (we discuss this below). Most individual samples follow the mass–metallicity relation reasonably closely: several ALLSMOG galaxies, not detected in CO emission lie above the relation, while some LVL galaxies lie 0.2–0.5 dex below the relation.

The symbol colour-coding in Fig. 3 shows the molecular gas mass, as derived using the Wolfire et al. (2010) CO/H₂ conversion factor. A molecular gas ‘FMR’ effect would be apparent if galaxies at a constant stellar mass have an inverse relation between molecular

gas mass and metallicity.² Such a relation is difficult to discern by eye, due to both the uncertainty-driven scatter, and the strong relation between molecular gas mass and stellar mass. To make any potential trends clearer, we examine the relation between molecular gas mass and the *offset* from the mass–metallicity relation (which we calculate by performing a quadratic fit to the mass–metallicity relation defined by our combined sample). The quadratic fit used for calculating offsets is shown as a dashed line in Fig. 3 (note that we have flattened the fit at upper end, to maximize at the ‘saturation metallicity’, 12+log(O/H) = 9.1). The fit is in good agreement with the fit found for a far larger SDSS sample by Tremonti et al. (2004), but is shifted slightly towards higher metallicities at stellar masses $\log M_* > 10^{10} M_\odot$.

Fig. 4 (left-hand panel) shows the offset from the mass–metallicity relation, plotted against molecular gas mass. For legibility, we have only plotted error bars for the high-*z* galaxies, which have their metallicities measured using the [N II]/H α calibrator alone and as a result are more uncertain (due to the greater flux errors on the more distant objects, as well as the uncertainty due to the availability of just a single calibrator).

We find that there is a shallow, but clear, inverse dependence between molecular gas mass and the offset from the mass–metallicity relation. Fitting linear functions to the relation, we find a slope of $= -0.088 \pm 0.021$ (for the Wolfire et al. 2010 conversion factor; slopes derived using our other conversion factors are: Glover & Mac Low 2011 $= -0.078 \pm 0.019$; Narayanan et al. 2012 $= -0.098 \pm 0.020$; and Feldmann et al. 2012 $= -0.081 \pm 0.018$). There is therefore clear evidence for a molecular gas ‘FMR’ effect, whereby galaxies at a fixed stellar mass show an inverse dependence between their metallicity and their molecular gas mass.

Fig. 4 (right-hand panel) shows the offset from the mass–metallicity relation, plotted against total (i.e. H₂+H I) gas mass. For our high-*z* galaxies, we have assumed that their ISM is entirely molecular (i.e. their total gas mass is equivalent to their molecular gas mass). As for the molecular gas above, we find that for each of four metallicity-dependent conversion factors there is a shallow inverse dependence between total gas mass and the offset from the mass–metallicity relation. Given the dependence with molecular gas demonstrated above, and the dependence with atomic gas presented by Bothwell et al. (2013b), a dependence with total gas mass is of course unsurprising. Fitting linear functions the relation, we find a slope of $= -0.076 \pm 0.022$ (again, this is for the Wolfire et al. 2010 conversion factor; other slopes are: Glover & Mac Low 2011 $= -0.071 \pm 0.016$; Narayanan et al. 2012 $= -0.083 \pm 0.018$; and Feldmann et al. 2012 $= -0.077 \pm 0.017$). There is therefore also evidence for a total gas ‘FMR’ effect, whereby galaxies at a fixed stellar mass show an inverse dependence between their metallicity and their total (i.e. H₂+H I) gas mass.

3.1 Comparison to an analytical model

In Fig. 5, we have compared the right-hand panel of Fig. 4 to the prediction from the analytical ‘gas regulator’ model of Peng & Maiolino (2014). We have binned the model data ($\sim 5 \times 10^5$

² Note that we refer to the ‘FMR’ effect as being an inverse relation with metallicity at a given stellar mass; due to the low numbers of galaxies available with molecular gas measurements, we are unable to explore the potential redshift independence of our relations, another hallmark of the FMR.




Figure 4. The offset from the $z = 0$ mass–metallicity relation, plotting against molecular hydrogen mass (left-hand panel), and total gas mass (right-hand panel). In each plot, a linear fit is overlotted. It can be seen that there is an inverse correlation between mass–metallicity offset and both H_2 mass and total gas mass (so galaxies with lower than average gas masses lie systematically above the mass–metallicity relation).




Figure 5. The offset from the $z = 0$ mass–metallicity relation, plotted against total gas mass, for (left-hand panel) our observed sample, and (right-hand panel) calculated using the Peng & Maiolino (2014) gas regulator model. Model data are shown in bins of stellar mass of 0.5 dex width. The model predicts a strong inverse dependence between mass–metallicity offset within each stellar mass bin. Also shown is the predicted ‘quenching sequence’ (dashed line, with associated standard deviation indicated with dotted lines).

model galaxies) in stellar mass bins of width 0.5 dex, and colour-coded both the model tracks and the observational data by stellar mass.

The model makes two main predictions. First, the model predicts that within a stellar mass bin, the offset from the mass–metallicity relation does increase (in the negative direction, i.e. below the mass–metallicity relation) with increasing total gas mass. This is broadly the same trend as we have found for our observational data above. However, the model also demonstrates that the dependency of the mass–metallicity offset is far steeper within any individual stellar mass bin than it would be for the sample as a whole (due to the strong correlation between stellar mass and total gas mass). However, such a separation in stellar mass is not immediately clear in the observational data – there seems to be sufficient scatter in the gas mass–stellar-mass correlation that any potentially clear trends

are obscured. The model does demonstrate why, when considering the sample as a whole, we only see a shallow dependence between metallicity offset and gas mass.

4 RESULTS: PCA

The analysis contained within the previous sections suffers from two potential weaknesses. First, as previously discussed, the correlation between gas mass and stellar mass serves to erode any clear trends between mass–metallicity offset and gas mass; other than showing that the analytical model is capable of reproducing the observed data, it is challenging to quantify any trends. Secondly, the technique suffered from being parametric – that is, dependent on the assumption that some distribution exists between stellar mass and metallicity, and parameterising data points in terms of their

offset from a quadratic fit to that relation. In our case, the specific results obtained depend strongly on the form of the fit to the mass–metallicity relation. Ideally, we would like to frame the analysis in terms of a non-parametric fitting technique, which simply examines the correlations in the data without presupposing any specific relationship between them. One such technique is PCA.

PCA is a linear transformation technique, by which a set of physical variables are converted into a set of orthogonal, linearly uncorrelated components (called ‘principle components’) defined by a set of eigenvectors. The conversion is chosen so to ensure that the maximum possible variance in the data is contained within the first component, and each subsequent component contains as much variance as possible (with the constraint that each component is orientated orthogonally to every preceding component). In practice, PCA performs a coordinate transformation revealing the optimum ‘projection’ of a data set, and revealing which parameters are responsible for the variance in the sample. PCA is particularly useful for revealing any possible ‘dimensionality reduction’ – for example, revealing that a distribution forms a 2D ‘plane’ in 3D parameter space (as Hunt et al. 2012 found for stellar mass, SFR, and metallicity). PCA was used by both Lara-López et al. (2010) and Hunt et al. (2012) to examine the secondary dependence of SFR on the mass–metallicity relation.

Here, we perform PCA on our data, examining the stellar mass, metallicity, and a third parameter of interest. In turn, we will examine the molecular gas mass, the *total* gas mass, the SFR, and the SFE. We first normalize each parameter to the mean value for our combined sample:

$$\log(M_*)^{\text{PCA}} = \log(M_*) - 10.13$$

$$12 + \log(\text{O}/\text{H})^{\text{PCA}} = 12 + \log(\text{O}/\text{H}) - 8.95$$

$$\log(\text{SFE})^{\text{PCA}} = \log(\text{SFE}) + 8.68$$

$$\log(\text{SFR})^{\text{PCA}} = \log(\text{SFR}) - 0.39$$

$$\log(M_{\text{H}_2})^{\text{PCA}} = \log(M_{\text{H}_2}) - 9.07$$

$$\log(M_{\text{gas}})^{\text{PCA}} = \log(M_{\text{gas}}) - 9.71$$

We have accounted for uncertainty by adopting a Monte Carlo approach, performing 10^5 PCA iterations for each combination of parameters. For each iteration, each galaxy has the value of its physical parameters randomly perturbed by an amount following the respective error on each parameter. At the end of the 10^5 iterations, we take the mean and standard deviation of the resulting Eigenvector distribution to be our final Eigenvector values (and uncertainties thereon). In order to ensure we are not unduly influenced by outliers, we also perform sample bootstrapping during the Monte Carlo: for each iteration, we randomly sample (with replacement) our complete sample of galaxies, generating in each case a sample size equal to our original data set.

It must be noted that a potential weakness in the application of PCA to our data is that PCA can only describe data sets in terms of linear relationships between parameters – more complex distributions of data cannot be described in terms of a simple set of orthogonal eigenvectors. While linear relationships (such as the SFR- M_* ‘main sequence’) are ideal for modelling using PCA, applying the technique to non-linear correlations (such as the mass–metallicity relation) will, by definition, be somewhat inaccurate. In practice, this will have the effect of increasing the apparent scatter around

Table 1. Eigenvectors of the three principle components, for each of our parameter sets (stellar mass, metallicity, and a third parameter of interest – respectively, molecular gas mass, total gas mass, SFR, and SFE. Errors have been obtained via a Monte Carlo bootstrapping method, as described in the text.

Component	M_*	$M(\text{H}_2)$	$12+\log(\text{O}/\text{H})$
PC 1	$+0.578 \pm 0.040$	-0.807 ± 0.032	$+0.118 \pm 0.023$
PC 2	-0.760 ± 0.033	-0.585 ± 0.043	-0.280 ± 0.031
PC 3	$+0.295 \pm 0.027$	-0.072 ± 0.021	-0.952 ± 0.008
Component	M_*	$M(\text{gas})$	$12+\log(\text{O}/\text{H})$
PC 1	$+0.441 \pm 0.081$	-0.893 ± 0.041	$+0.085 \pm 0.023$
PC 2	-0.858 ± 0.045	-0.448 ± 0.083	-0.249 ± 0.022
PC 3	$+0.261 \pm 0.024$	-0.037 ± 0.015	-0.964 ± 0.007
Component	M_*	SFR	$12+\log(\text{O}/\text{H})$
PC 1	$+0.513 \pm 0.056$	-0.852 ± 0.036	$+0.100 \pm 0.027$
PC 3	-0.816 ± 0.036	-0.521 ± 0.059	-0.249 ± 0.021
PC 3	$+0.265 \pm 0.021$	-0.045 ± 0.014	-0.962 ± 0.005
Component	M_*	SFE	$12+\log(\text{O}/\text{H})$
PC 1	$+0.904 \pm 0.042$	-0.368 ± 0.114	$+0.214 \pm 0.023$
PC 2	-0.357 ± 0.113	-0.929 ± 0.044	-0.092 ± 0.032
PC 3	$+0.233 \pm 0.025$	-0.007 ± 0.004	-0.972 ± 0.006

the component vectors. Given the relatively low numbers of galaxies in our sample, it is likely that the uncertainty added by forcing linear relations on to the data is not larger than the uncertainty inherent in the distribution of the data (as revealed by our Monte Carlo approach). We therefore continue to perform PCA on our data, but caution the reader that some uncertainty may be added due to non-linearity in some underlying correlations.

The results are discussed below. Fig. 6 shows the results of performing PCA on the parameters stellar mass, metallicity, and molecular gas mass. Figs 7, 8, and 9 show the results when using total gas mass, SFR, and SFE (respectively) as the third parameter. Table 1 lists the values of the Eigenvectors of the components in each instance.

In each of the four cases, the PCA results do indeed suggest that the galaxy form a 2D plane in the parameter space, with just ~ 1.5 –3 per cent of the total variation occurring in the third principle component. As noted by Hunt et al. (2012), with very little of the sample variance contained within the third principle component, it is a useful tool for examining the optimal relationship between the three parameters of interest. In each of our cases, the third parameter is highly dominated by metallicity, with only minor contributions from the other parameters. We can therefore ‘solve’ for metallicity, by setting the third principle component equal to zero (which is valid at the ~ 1.5 –3 per cent level), allowing us to examine the effect of each parameter (stellar mass, molecular gas mass, total gas mass, SFR, and SFE) on metallicity.

Molecular gas mass. The PCA results for molecular gas are shown in Fig. 6. Approximately 80 per cent of the variance is contained within the first component, and ~ 97 per cent of the variance is contained within the first two. The first component is defined mainly in terms of stellar mass and molecular gas mass (molecular gas mass being the dominant contributor), with a small contribution from metallicity. The second component is similarly defined, with the contribution from metallicity being a little greater. The third component, which accounts for just 2.8 per cent of the sample variation, is dominated by metallicity (telling us that that metallicity has the minority contribution to the total sample variance).




Figure 6. Three projections of the three space defined by the principle components derived in Section 4. The inset legends above the plots give the definitions of the principle components, in terms of stellar mass (M_*), molecular gas mass (M_{H2}), and metallicity (Z).




Figure 7. Three projections of the three space defined by the principle components derived in Section 4. The inset legends above the plots give the definitions of the principle components, in terms of stellar mass (M_*), total gas mass (M_{gas}), and metallicity (Z).

We now set the third principle component to zero. Here, the third principle component is defined as

$$PC3 = 0.295 (M_*)^{PCA} - 0.072 (M_{H2})^{PCA} - 0.952 12 + \log(O/H)^{PCA} \quad (4)$$

Setting this to zero implies that

$$12 + \log(O/H) = 0.31(\log M_*) - 0.08(\log M_{H2}) + 6.53 \quad (5)$$

That is, the metallicity is primarily determined by the stellar mass (i.e. the mass–metallicity relation), with a secondary dependence on

the molecular gas mass. This secondary dependence on molecular gas mass is approximately 22 per cent times as strong as the primary dependence on stellar mass.

Total gas mass. The PCA results for total gas mass are shown in Fig. 7. ~ 73 per cent of the variance is contained within the first component, and ~ 98 per cent of the variance is contained within the first two. The first component is defined mainly in terms of stellar mass and total gas mass, with a small contribution from metallicity. And again, the second component is similarly defined, with the contribution from metallicity being a little greater. The third component, which here accounts




Figure 8. Three projections of the three space defined by the principle components derived in Section 4. The inset legends above the plots give the definitions of the principle components, in terms of stellar mass (M_*), SFR (SFR), and metallicity (Z).




Figure 9. Three projections of the three space defined by the principle components derived in Section 4. The inset legends above the plots give the definitions of the principle components, in terms of stellar mass (M_*), SFE, and metallicity (Z). Metallicity has a weaker effect on the distribution, which can be mainly defined in terms of M_* and SFE.

for just 2.5 per cent of the sample variation, is dominated by metallicity.

Again, we set the third principle component to zero. Here, the third principle component is defined as

$$\text{PC3} = 0.261 (M_*)^{\text{PCA}} - 0.038 (M_{\text{gas}})^{\text{PCA}} - 0.964 \, 12 + \log(\text{O}/\text{H})^{\text{PCA}} \quad (6)$$

Setting this to zero implies that

$$12 + \log(\text{O}/\text{H}) = 0.27(\log M_*) - 0.04(\log M_{\text{gas}}) + 6.60 \quad (7)$$

That is, the metallicity is primarily determined by the stellar mass, with a secondary dependence on the total gas mass. This secondary dependence on total gas mass is approximately 13 per cent times as strong as the primary dependence on stellar mass. This shows that the metallicity dependence with the molecular gas content (discussed in the previous subsection) is stronger than with the total gas content.

Star formation rate. The PCA results for SFR are shown in Fig. 8. ~73 per cent of the variance is contained within the first component, and ~97 per cent of the variance is contained within the first two.

Table 2. Physical parameters (stellar mass, metallicity, SFR, and $M(\text{H}_2)$) derived using the Wolfire et al. 2010 CO/ H_2 conversion factor) for the galaxies in this work.

$\log M_*$ [M_\odot]	$12+\log(\text{O}/\text{H})$	SFR [M_\odot/yr]	$M(\text{H}_2)$ [M_\odot]	Source
9.70	8.89	0.869	8.27	ALLSMOG
9.61	9.15	2.32	9.20	ALLSMOG
9.58	8.98	0.210	7.85	ALLSMOG
9.94	9.08	3.84	8.80	ALLSMOG
9.84	8.99	1.24	8.90	ALLSMOG
9.73	8.81	1.16	8.93	ALLSMOG
9.80	9.08	1.29	8.55	ALLSMOG
9.85	9.11	1.18	8.98	ALLSMOG
9.91	8.95	1.54	8.91	ALLSMOG
9.70	9.01	1.06	8.57	ALLSMOG
9.44	8.71	2.17	8.91	ALLSMOG
9.89	8.97	1.72	8.75	ALLSMOG
9.99	9.08	1.05	8.64	ALLSMOG
9.64	8.89	1.13	8.54	ALLSMOG
9.98	9.07	1.43	8.92	ALLSMOG
9.80	8.98	1.05	8.34	ALLSMOG
9.32	8.91	0.299	7.60	ALLSMOG
9.91	9.09	1.39	9.06	ALLSMOG
9.96	9.12	0.160	8.47	ALLSMOG
9.68	9.01	0.358	8.32	ALLSMOG
9.98	9.03	1.89	8.52	ALLSMOG
9.74	8.92	1.79	8.52	ALLSMOG
9.57	8.80	0.526	8.36	ALLSMOG
9.78	9.00	1.81	8.68	ALLSMOG
9.36	8.91	0.221	<7.75	ALLSMOG
9.11	8.61	0.207	<7.94	ALLSMOG
9.42	8.74	1.05	<8.40	ALLSMOG
8.61	8.66	0.0551	<8.33	ALLSMOG
8.75	8.64	0.151	<8.44	ALLSMOG
8.57	8.61	0.129	<8.42	ALLSMOG
9.96	8.85	1.30	<8.38	ALLSMOG
9.51	8.84	1.01	<8.55	ALLSMOG
9.95	8.85	1.20	<8.49	ALLSMOG
8.67	8.52	0.0902	<8.45	ALLSMOG
9.51	8.80	3.70	<8.52	ALLSMOG
8.89	8.60	0.140	<8.34	ALLSMOG
8.99	8.60	0.305	<8.22	ALLSMOG
8.81	9.00	0.314	<8.08	ALLSMOG
8.96	8.65	0.162	<8.04	ALLSMOG
8.54	8.55	0.0357	<8.50	ALLSMOG
9.06	8.79	12.0	<7.95	ALLSMOG
10.17	8.95	2.11	8.87	COLD GASS
10.05	8.93	3.47	8.87	COLD GASS
10.08	8.99	2.19	8.91	COLD GASS
10.81	9.15	1.35	9.14	COLD GASS
10.74	9.17	4.41	9.13	COLD GASS
10.67	9.07	7.40	9.73	COLD GASS
10.74	9.07	9.33	9.85	COLD GASS
10.90	9.10	6.59	9.81	COLD GASS
10.26	9.08	0.910	8.36	COLD GASS
10.41	9.15	2.48	8.80	COLD GASS
10.55	9.13	2.41	9.14	COLD GASS
10.37	9.03	3.40	9.21	COLD GASS
10.48	9.10	1.13	9.03	COLD GASS
10.10	9.09	1.38	8.96	COLD GASS
10.53	9.13	26.8	9.30	COLD GASS
10.07	8.88	2.18	8.85	COLD GASS
10.11	9.08	2.42	9.15	COLD GASS
10.55	9.06	9.75	9.59	COLD GASS
10.37	9.04	8.57	9.46	COLD GASS

Table 2 – *continued*

$\log M_*$ [M_\odot]	$12+\log(\text{O}/\text{H})$	SFR [M_\odot/yr]	$M(\text{H}_2)$ [M_\odot]	Source
10.06	9.00	1.94	8.97	COLD GASS
10.11	9.08	2.53	8.93	COLD GASS
10.20	9.00	0.810	8.90	COLD GASS
10.38	9.10	2.89	9.35	COLD GASS
10.01	9.07	1.28	8.68	COLD GASS
10.32	8.87	10.0	9.58	COLD GASS
10.98	9.07	3.75	9.84	COLD GASS
10.27	9.02	1.00	9.17	COLD GASS
10.64	9.09	3.86	9.52	COLD GASS
10.03	8.95	1.24	9.49	COLD GASS
10.59	9.05	7.31	9.63	COLD GASS
10.24	9.10	0.110	8.75	COLD GASS
10.02	8.98	0.990	8.60	COLD GASS
10.39	9.04	3.38	9.29	COLD GASS
10.44	9.00	16.0	9.51	COLD GASS
10.80	9.17	2.72	9.18	COLD GASS
10.29	9.13	1.45	8.80	COLD GASS
10.98	9.15	0.620	8.91	COLD GASS
10.70	9.14	3.61	9.53	COLD GASS
10.09	9.05	5.72	9.23	COLD GASS
10.17	9.07	2.41	8.81	COLD GASS
10.77	9.07	5.51	9.68	COLD GASS
10.91	9.05	7.11	9.39	COLD GASS
10.60	9.18	3.46	9.07	COLD GASS
10.49	9.05	13.7	9.72	COLD GASS
10.15	9.03	2.11	8.86	COLD GASS
10.12	9.06	2.03	9.02	COLD GASS
10.77	9.04	6.84	9.76	COLD GASS
10.28	9.00	9.40	9.63	COLD GASS
11.03	9.08	4.80	9.61	COLD GASS
10.85	8.97	3.50	9.61	COLD GASS
10.95	9.19	3.47	9.63	COLD GASS
10.15	9.05	2.60	9.17	COLD GASS
10.99	8.92	0.410	9.97	COLD GASS
10.31	9.04	4.00	9.28	COLD GASS
10.18	8.96	9.73	9.42	COLD GASS
10.44	9.15	9.92	9.49	COLD GASS
11.33	9.14	1.92	9.35	COLD GASS
10.91	9.08	2.77	9.74	COLD GASS
10.41	9.15	3.22	9.10	COLD GASS
10.18	8.92	1.01	9.02	COLD GASS
10.76	9.07	5.74	9.56	COLD GASS
10.42	9.20	4.50	9.34	COLD GASS
10.77	9.05	4.72	9.73	COLD GASS
10.87	9.08	5.43	9.53	COLD GASS
10.57	9.10	1.93	8.96	COLD GASS
10.54	9.16	1.46	8.87	COLD GASS
11.03	9.18	1.47	8.91	COLD GASS
10.46	9.09	0.240	8.51	COLD GASS
10.28	9.13	2.41	8.77	COLD GASS
10.04	9.06	2.40	9.04	COLD GASS
10.02	8.99	0.350	8.43	COLD GASS
10.05	9.03	1.24	8.90	COLD GASS
10.56	9.16	1.72	8.67	COLD GASS
10.64	9.14	7.00	9.69	COLD GASS
10.10	8.98	2.14	9.27	COLD GASS
10.07	9.10	1.43	8.59	COLD GASS
10.13	9.06	1.57	8.98	COLD GASS
10.05	9.03	1.68	8.90	COLD GASS
10.60	9.02	3.44	9.51	COLD GASS
10.25	9.14	1.45	8.67	COLD GASS
10.09	8.96	0.900	<8.88	COLD GASS

Table 2 – continued

$\log M_*$ [M_\odot]	12+log(O/H)	SFR [M_\odot/yr]	M(H ₂) [M_\odot]	Source
11.18	9.14	2.25	<9.17	COLD GASS
10.24	9.04	0.350	<8.93	COLD GASS
10.01	9.20	2.17	<9.10	COLD GASS
10.03	9.12	0.0600	<8.83	COLD GASS
10.09	8.94	0.000	<8.62	COLD GASS
11.01	9.12	0.520	<9.16	COLD GASS
10.89	9.17	0.0400	<9.09	COLD GASS
11.13	9.19	0.430	<9.25	COLD GASS
10.79	9.14	1.19	<9.12	COLD GASS
11.08	9.15	0.790	<9.18	COLD GASS
10.11	8.95	0.0600	<8.65	COLD GASS
9.46	8.81	3.04	8.89	HRS
9.69	8.94	6.00	8.67	HRS
10.2	9.02	13.8	9.34	HRS
10.2	8.96	16.5	9.23	HRS
9.77	8.76	8.34	9.16	HRS
10.0	9.01	5.02	9.10	HRS
9.42	8.83	3.44	8.45	HRS
9.25	8.68	1.05	8.62	HRS
9.28	8.85	1.80	8.47	HRS
9.20	8.79	1.10	8.34	HRS
9.21	8.62	2.42	8.39	HRS
9.21	8.57	3.66	8.47	HRS
9.22	8.69	2.86	8.78	HRS
10.4	9.05	15.9	9.66	HRS
9.47	8.68	2.19	8.43	HRS
9.60	8.84	3.83	8.33	HRS
9.45	8.84	1.55	<8.31	HRS
9.17	8.74	7.54	<8.16	HRS
8.94	8.92	2.04	<8.79	HRS
9.27	8.59	3.63	<8.56	HRS
9.20	8.82	0.701	<8.47	HRS
9.23	8.73	1.61	<7.98	HRS
9.14	8.60	0.983	<8.71	HRS
11.48	8.99	4.29	9.36	LVL
9.736	8.36	0.37	7.85	LVL
10.86	8.90	2.45	9.22	LVL
10.83	9.31	5.20	9.12	LVL
9.485	8.64	0.13	7.22	LVL
8.407	8.01	0.05	8.14	LVL
8.450	8.01	0.07	8.19	LVL
9.976	8.76	0.37	8.35	LVL
10.74	9.09	0.97	8.67	LVL
11.12	9.04	0.65	8.66	LVL
11.10	9.13	3.10	9.51	LVL
8.582	8.23	0.04	7.76	LVL
9.722	8.65	0.17	6.98	LVL
8.769	8.25	0.16	7.04	LVL
9.296	8.32	0.31	8.78	LVL
9.611	8.80	0.11	7.21	LVL
11.01	8.89	1.91	8.77	LVL
9.382	8.31	0.74	7.92	LVL
9.376	8.64	0.28	7.76	LVL
10.64	9.01	0.57	8.59	LVL
10.45	9.01	0.47	8.60	LVL
10.47	9.05	245	10.75	MS
10.43	8.95	30	10.44	MS
9.780	8.73	33	10.85	MS
10.75	8.73	97	10.70	MS
10.75	8.84	127	11.07	MS
11.27	8.61	141	11.07	MS
11.38	8.96	117	11.02	MS

Table 2 – continued

$\log M_*$ [M_\odot]	12+log(O/H)	SFR [M_\odot/yr]	M(H ₂) [M_\odot]	Source
11.17	8.98	92	10.80	MS
11.23	9.01	141	11.17	MS
10.79	8.75	540	11.54	SMG
11.20	9.09	810	11.36	SMG
10.30	8.75	1070	11.02	SMG
10.86	8.74	390	11.48	SMG
10.59	8.91	680	10.72	SMG
10.99	9.07	2890	11.49	SMG
11.01	9.09	1260	11.39	SMG
11.13	8.86	950	11.07	SMG

The first component is defined mainly in terms of stellar mass and SFR, with a small contribution from metallicity. And again, the second component is similarly defined, with the contribution from metallicity being a little greater. The third component, which here accounts for just 2.8 per cent of the sample variation, is dominated by metallicity. These results are consistent with the work done by Hunt et al. (2012), who used PCA to examine correlations between stellar mass, SFR, and metallicity for a sample of metal-poor starbursts.

Setting the third principle component to zero. Here, the third principle component is defined as

$$\text{PC3} = 0.265 (M_*)^{\text{PCA}} - 0.045 (\text{SFR})^{\text{PCA}} - 0.963 \text{12} + \log(\text{O}/\text{H})^{\text{PCA}} \quad (8)$$

Setting this to zero implies that

$$\text{12} + \log(\text{O}/\text{H}) = 0.28 (\log M_*) - 0.05(\log \text{SFR}) + 6.14. \quad (9)$$

That is, the metallicity is primarily determined by the stellar mass, with a secondary dependence on the SFR. This secondary dependence on SFR is approximately 16 per cent times as strong as the primary dependence on stellar mass. As before, this dependence on the SFR is weaker than the dependence on the molecular gas content.

Star formation efficiency. The PCA results for SFE are shown in Fig. 9. Approximately 66 per cent of the variance is contained within the first component, and ~ 97 per cent of the variance is contained within the first two. The first component is defined mainly in terms of stellar mass and SFE, with a slightly smaller contribution from metallicity. The second component is similarly defined, with the contribution from metallicity being a somewhat less. The third component, which here accounts for 3.0 per cent of the sample variation, is dominated by metallicity, with only a very minor contribution from SFE.

Again, we set the third principle component to zero. Here, the third principle component is defined as

$$\text{PC3} = 0.233 (M_*)^{\text{PCA}} - 0.007 (\text{SFE})^{\text{PCA}} - 0.972 \text{12} + \log(\text{O}/\text{H})^{\text{PCA}} \quad (10)$$

Setting this to zero implies that

$$\text{12} + \log(\text{O}/\text{H}) = 0.24(\log M_*) - 0.008(\log \text{SFE}) + 6.45. \quad (11)$$

That is, the metallicity is primarily determined by the stellar mass, with negligible secondary dependence on the SFE: the secondary




Figure 10. The strength of the influence on the mass–metallicity relation of molecular gas mass (green line), total gas mass (blue line), SFR (red line), and SFE (black line). The strength of the influence is quantified as μ – see equation (12). Results for four recent metallicity-dependent CO/H₂ conversion factors are shown. In each case, the strongest effect is found to be with gas content (either molecular or total). The smallest influence on the mass–metallicity relation is found with SFE.

dependence on SFE is approximately 3 per cent times as strong as the primary dependence on stellar mass. This clearly indicates that there is no correlation between SFE and metallicity, once the dependence on stellar mass is taken into account. This will be discussed further in the next section.

5 DISCUSSION

5.1 The effect of a changing CO/H₂ conversion factor

Thus far, all PCA results have been calculated using the metallicity-dependent CO/H₂ conversion factor presented by Wolfire et al. (2010; Table 2). It is, however, important to investigate the extent to which these results are robust to a range of conversion factor prescriptions.

We perform the same PCA steps for three further metallicity-dependent CO/H₂ conversion factors: Glover & Mac Low (2011), Feldmann et al. (2012), and Narayanan et al. (2012). In the interest of saving space, we do not repeat the above discussion for each case. Nevertheless, each conversion factor produces highly similar behaviour: examining each secondary dependence in turn (molecular gas mass, *total* gas mass, SFR, and SFE), we find that the distribution of data does form a 2D plane in 3D parameter space, with between 2 per cent – 5 per cent of the sample variation being contained within the first two principle components.

We focus on the differences produced by the final step in the analysis – that by setting the third principle component to zero, the metallicity can be defined in terms of the stellar mass, with a secondary modifying term coming from one of the parameters listed above (in the original formulation of the FMR by Mannucci et al. 2010 and Lara-López et al. 2010, SFR was used for this third parameter).

As above, we parametrize the strength of the effect of the third parameter (either $M(\text{H}_2)$, $M(\text{gas})$, SFR, or SFE) on the metallicity by setting the third principle component to zero, and finding the resultant expression for the metallicity:

$$12 + \log(\text{O}/\text{H}) = \log(M_*) - \mu \log(X), \quad (12)$$

where X is, in turn, $M(\text{H}_2)$, $M(\text{gas})$, SFR, or SFE. Fig. 10 shows the values of μ we find for each parameter. All values of μ are < 1 ,

implying that in all cases the dominant driver of metallicity variations is the stellar mass. For each of the four CO/H₂ conversion factors, we find that gas content is the most influential ‘secondary parameter’. For three out of four of the conversion factor prescriptions (Wolfire et al. 2010, Glover & Mac Low 2011, and Narayanan et al. 2012), it is the molecular gas that has the most influence on metallicity (after stellar mass). For the remaining conversion factor prescription – Feldmann et al. (2012) – it is the *total* gas content that is the strongest secondary parameter (though it is comparable to the effect of molecular gas within the uncertainties on μ , which are typically ± 0.05). But, independent of the choice of conversion factor, we find that the strongest ‘FMR’ effect is to be found with gas content.

5.2 Comparison to the SFR–FMR

The strength of SFR as a secondary parameter is somewhat less than gas content, with $\mu_{\text{SFR}} \sim 0.17$ (small variations in μ_{SFR} shown in Fig. 10 are due to randomness introduced by the bootstrapping technique). We note that this value is significantly smaller than the value of μ found by Mannucci et al. (2010): they express metallicity as a function of stellar mass and SFR:

$$12 + \log(\text{O}/\text{H}) = \log(M_*) - 0.32 \log(\text{SFR}) \quad (13)$$

We therefore find the size of the effect of SFR on metallicity to be approximately 50 per cent of that found by Mannucci et al. (2010). This discrepancy is far larger than can be accounted for by sample uncertainty; our bootstrapping analysis estimates a combined uncertainty on the influence of SFR of ~ 30 per cent ($\mu_{\text{SFR}} = 0.17 \pm 0.05$).

One potential resolution to the conflict lies in the method used to calculate the SFRs. Mannucci et al. (2010) took their sample from SDSS, using the SFRs and strong line fluxes as provided by the SDSS spectroscopic fibre. SDSS calculates its pipeline SFRs by fitting to optical strong lines (with the H α having the most influence). As such (a) previously, SFRs and metallicities were calculated from matched-aperture observations, and (b) the same optical strong lines were used to calculate both SFRs and metallicities, which could introduce a codependency. Both of these effects could result in the correlation between SFR and metallicity being artificially tightened. It has been shown that when calculating SFRs by adopting *integrated* SFRs, corrected for fibre-aperture effects, the SFR–FMR effect weakens considerably (Bothwell et al. 2013b; Zahid et al. 2014).

In this work, we have used both galaxies with SDSS-SFRs (galaxies taken from the ALLSMOG and COLD GASS surveys), and galaxies with SFRs calculated with other methods (we used a combination of IR and UV fluxes for the HRS and LVL samples, the $z \sim 2$ discs have SFRs derived from fitting to a combination of UV, optical continuum, H α , and 24 μm continuum fluxes, and the $z \sim 2$ SMGs have SFRs derived using IR fluxes, via the far-IR–radio correlation). These disparate methods, while all being effective probes of the total SFR, will clearly not introduce the same codependency as taking all values from the same SDSS spectra. This weakens any correlations between SFR and metallicity which were previously spuriously enhanced.

5.3 Comparison with an analytical model

A key prediction of the model we discuss in Section 3.2.1 is the existence of a ‘quenching sequence’, populated by galaxies which are elevated *above* the mass–metallicity relation. Within the framework of the model, the only mechanism able to elevate galaxies significantly above the mass–metallicity relation is

‘strangulation’ – the cessation of gas infall – which leads first to the build-up of metals due to star formation (with a lack of metal-poor inflowing gas acting to dilute the ISM), and ultimately to the shutting down of star formation (‘quenching’). Recently, Peng, Maiolino & Cochrane (2015) have shown that the comparison of stellar metallicities between passive and star-forming galaxies strongly support strangulation as the main quenching mechanism for galaxies with mass $< 10^{11} M_{\odot}$. Being an emission line-selected sample, none of our sample galaxies are currently fully quenched. The model predicts, however, that the approximately seven galaxies elevated above our relation are essentially analogues of ‘green valley’ galaxies, identified via their metallicity and gas mass, which have recently undergone strangulation and are in the processes of becoming quenched and dead.

It is important to investigate whether the model is doing a good job of explaining the scatter in the data. Randomness in the model is introduced by allowing the gas inflow rate to vary by a factor of 2 – this introduces scatter in both metallicity and gas content. If it can be seen that the scatter in the observed data is greater than that contained in the model (allowing for observational uncertainties), it is likely that real gas inflow rates vary by a factor of > 2 . We compare the model to the data as follows. For each observed galaxy, we identify all model galaxies with the same stellar mass and metallicity (within bins of 0.05 dex). We then compare the total gas mass of the real galaxy to the mean gas mass of the (mass and metallicity matched) model galaxies. We find a mean discrepancy between the model and observed gas mass of 0.49 dex. This must be compared, though, to the variance in gas mass contained within the model itself. Within each 0.05 dex bin of stellar mass and metallicity, the standard deviation of model gas masses is 0.41 dex. That is, the mean discrepancy between the analytical model and the data is only slightly more than the variance contained within the model itself. Allowing for typical observational uncertainties on the gas mass the model provides a good match to the data, suggesting that the assumptions of the model (i.e. that gas inflow rate varies by up to a factor of 2) are sufficient to explain the observed scatter.

5.4 The connection between metallicity and SFE

In all cases, by far the weakest ‘FMR’ effect is found with the SFE. Across all CO/H₂ conversion factors, the SFE and metallicity are only very weakly connected. In other words, the Schmidt–Kennicutt relation does not depend on metallicity. To date, the relationship between metallicity and SFE has been challenging to examine, due to the strong correlation between metallicity and stellar mass. The molecular gas consumption time ($\tau_{\text{H}_2} \equiv 1/\text{SFE}$) is observed to vary with stellar mass (Saintonge et al. 2011b; Bothwell et al. 2014), a phenomenon which Saintonge et al. (2011b) attribute to the presence of increasingly ‘bursty’ star formation histories towards lower halo masses. It is due to the strong covariance between metallicity and stellar mass that a technique like PCA is required, in order to break the mass–metallicity degeneracy and isolate the effects of individual parameters. Simply plotting metallicity against SFE for our sample would result in a good, yet spurious, correlation.

At first glance, a lack of correlation between metallicity and SFE appears somewhat surprising: metal lines act as an efficient cooling mechanism for the ISM, and given a lack of metals the ISM cannot effectively cool, fragment into molecular clouds, and form stars. This was the conclusion drawn by Shi et al. (2014), who found extremely low SFEs in two local metal-poor dwarf galaxies (these low SFEs result from a large reservoir of CO-dark molecular gas, which Shi et al. 2014 trace using dust emission). However, the low-

metallicity regime in which the Shi et al. (2014) study was carried out may differ significantly from the ISM conditions within the galaxies analysed in this work, and it is unclear if the results are applicable; many models predicting reduced SFE due to inefficient cooling in low-metallicity environments (i.e. Krumholz, McKee & Tumlinson 2009) deal with galaxies at such low metallicities that the ISM is entirely atomic.

There are few explorations of the connection between SFE and metallicity in the molecular regime. Dib et al. (2011) present a semi-analytic model of protocluster clumps which predicts an *increase* in SFE as metallicity decreases, primarily due to the weaker stellar winds at low metallicity (which results in a less thorough evacuation of gas in low-metallicity star-forming clumps). Observationally, Dib et al. (2011) find a trend supporting this, which is, however, based on just three galaxies (the SMC, M33, and NGC6822).

To date, therefore, there has been no clear observational consensus as to the effect of metallicity on SFE, with previous studies having very small sample sizes (2–3 galaxies) and reaching conflicting results. The results presented in this work, which find a negligible connection between SFE and metallicity, represent the first investigation of this issue with a significant sample size.

There are also many physical effects potentially governing the effect of metallicity on SFE (gas cooling and stellar wind efficiency being just two), and no clear theoretical consensus on which effects will dominate. Phenomenologically, the weakness of the connection between SFE and metallicity follows simply from the fact that metallicity varies with molecular gas content and SFR in similar ways; a secondary dependence in the mass–metallicity relation is observed with both molecular gas and SFR (though molecular gas has the stronger effect). As this dependence is in the same direction for each parameter – at a given stellar mass, galaxies with either increased SFR or increased M(H₂) have lower metallicity – when considering the ratio of these two quantities (the SFE), the effect nearly cancels out. As a result, SFE and metallicity are only very weakly connected in the samples considered in this work. Physically, it may be that a combination of metallicity-dependent processes (e.g. weak stellar winds, inefficient gas cooling) conspire to leave no connection between SFE and metallicity. Such a conclusion, however, would require theoretical investigation beyond the scope of this work.

6 CONCLUSIONS

In this work, we have presented an analysis of the connection between the gas content (both molecular and total) and metallicity of galaxies in samples from $0 < z < 2$. We have explored the effect of various metallicity-dependent CO/H₂ conversion factors on the Schmidt–Kennicutt relation. Conversely, we have also investigated the effect of gas content on the mass–metallicity relation, the most commonly used metallicity–scaling relation. Finally, we use PCA to statistically analyse these parameters within a non-parametric framework. Our main conclusions are as follows.

- (i) We demonstrate the existence of a systematic ‘fundamental metallicity relation’ effect between molecular gas mass, stellar mass, and metallicity, by which at a fixed stellar mass, galaxies with higher H₂ mass lie systematically below the mass–metallicity relation.
- (ii) We use PCA to explore the correlations between stellar mass, metallicity, and a third parameter (respectively, molecular gas content, total gas content, SFR, and SFE) in a non-parametric way. We find strong evidence for secondary dependences with both gas

content and SFR, with the effect of gas content being stronger independent of the choice of CO/H₂ conversion factor. We conclude that gas content is the driver of the ‘fundamental metallicity relation’, with the (more commonly used) SFR–FMR being simply a consequence due to the Schmidt–Kennicutt relation.

(iii) We find a very negligible connection between gas-phase metallicity and SFE; that is, the Schmidt–Kennicutt relation has no dependence on metallicity. This result stands in opposition to some recent findings, which were conducted with far smaller sample sizes than used in this work.

ACKNOWLEDGEMENTS

We thank the anonymous referee who provided comments which improved this manuscript. This research has made use of NASA’s Astrophysics Data System.

REFERENCES

- Ascasibar Y., Gavilán M., Pinto N., Casado J., Rosales F., Díaz A. I., 2015, *MNRAS*, 448, 2126
- Baldwin J. A., Phillips M. M., Telervich R., 1981, *PASP*, 93, 5
- Bell E. F., de Jong R. S., 2001, *ApJ*, 550, 212
- Bendo G. J., Galliano F., Madden S. C., 2012, *MNRAS*, 423, 197
- Bolatto A. D., Wolfire M., Leroy A. K., 2013, *ARA&A*, 51, 207
- Boselli A. et al., 2010, *PASP*, 122, 261
- Boselli A., Hughes T. M., Cortese L., Gavazzi G., Buat V., 2013, *A&A*, 550, A114
- Boselli A., Cortese L., Boquien M., 2014, *A&A*, 564A, 65
- Bothwell M. S., Kennicutt R. C., Lee J. C., 2009, *MNRAS*, 400, 154
- Bothwell M. S. et al., 2013a, *MNRAS*, 429, 3047
- Bothwell M. S., Maiolino R., Kennicutt R., Cresci G., Mannucci F., Marconi A., Ciccone C., 2013b, *MNRAS*, 433, 1425
- Bothwell M. S. et al., 2014, *MNRAS*, 445, 2599
- Brinchmann J., Charlot S., White S. D. M., Tremonti C., Kauffmann G., Heckman T., Brinkmann J., 2004, *MNRAS*, 351, 1151
- Burgarella D., Buat V., Iglesias-Páramo J., 2005, *MNRAS*, 360, 1413
- Catinella B. et al., 2010, *MNRAS*, 403, 683
- Chapman S. C., Blain A. W., Smail I., Ivison R. J., 2005, *ApJ*, 622, 772
- Cortese L. et al., 2012, *A&A*, 544, A101
- Davé R., Finlator K., Oppenheimer B. D., 2012, *MNRAS*, 421, 98
- Dayal P., Ferrara A., Dunlop J. S., 2013, *MNRAS*, 430, 2891
- Dib S., Piau L., Mohanty S., Braine J., 2011, *MNRAS*, 415, 3439
- Feldmann R., Gnedin N. Y., Kravtsov A. V., 2012, *ApJ*, 747, 124
- Glover S. C. O., Mac Low M.-M., 2011, *MNRAS*, 412, 337
- Hainline L. J., Blain A. W., Smail I., Alexander D. M., Armus L., Chapman S. C., Ivison R. J., 2011, *ApJ*, 740, 96
- Ho I., Kudritzki R.-P., Kewley L. J., Zahid H. J., Dopita M. A., Bresolin F., Rupke D. S. N., 2015, *MNRAS*, 448, 2030
- Hunt L. et al., 2012, *MNRAS*, 427, 906
- Iglesias-Páramo J. et al., 2006, *ApJS*, 164, 38
- Kauffmann G. et al., 2003a, *MNRAS*, 341, 54
- Kauffmann G. et al., 2003b, *MNRAS*, 346, 1055
- Kennicutt R. C., Jr, 1998, *ApJ*, 498, 541
- Kewley L. J., Jansen R. A., Geller M. J., 2005, *PASP*, 117, 227
- Kroupa P., 2001, *MNRAS*, 322, 231
- Krumholz M. R., McKee C. F., Tumlinson J., 2009, *ApJ*, 699, 850
- Lara-López M. A., Hopkins A. M., 2014, in *Rev. Mex. Astron. Astrofis. Ser. Conf. Vol. 44, Galaxy And Mass Assembly (GAMA): The Connection Between Metals, Specific SFR and H I Gas in Galaxies: the Z-SSFR Relation*. *Revista Mexicana de Astronomía y Astrofísica*, based at the Instituto de Astronomía, UNAM, p. 179
- Lara-López M. A. et al., 2010, *A&A*, 521, L53
- Lee J. C. et al., 2009, *ApJ*, 706, 599
- Magrini L. et al., 2012, *MNRAS*, 427, 1075
- Maiolino R. et al., 2008, *A&A*, 488, 463
- Mannucci F., Cresci G., Maiolino R., Marconi A., Gnerucci A., 2010, *MNRAS*, 408, 2115
- Marble A. R. et al., 2010, *ApJ*, 715, 506
- Narayanan D., Krumholz M. R., Ostriker E. C., Hernquist L., 2012, *MNRAS*, 421, 3127
- Newman S. F. et al., 2012, *ApJ*, 761, 43
- Obreja A., Brook C. B., Stinson G., Domínguez-Tenreiro R., Gibson B. K., Silva L., Granato G. L., 2014, *MNRAS*, 442, 1794
- Planck Collaboration XIII, 2015, preprint ([arXiv:e-prints](https://arxiv.org/abs/1502.01584))
- Peng Y.-j., Maiolino R., 2014, *MNRAS*, 443, 3643
- Peng Y., Maiolino R., Cochrane R., 2015, *Nature*, 521, 192
- Saintonge A. et al., 2011a, *MNRAS*, 415, 32
- Saintonge A. et al., 2011b, *MNRAS*, 415, 61
- Salim S., Rich R. M., Charlot S., Brinchmann J., Johnson B. D., Schiminovich D., 2007, *ApJS*, 173, 267
- Salpeter E. E., 1955, *ApJ*, 121, 161
- Sánchez S. F. et al., 2014, *A&A*, 563, A49
- Schmidt M., 1959, *ApJ*, 129, 243
- Shi Y., Armus L., Helou G., Stierwalt S., Gao Y., Wang J., Zhang Z.-Y., Gu Q., 2014, *Nature*, 514, 335
- Steidel C. C., Shapley A. E., Pettini M., Adelberger K. L., Erb D. K., Reddy N. A., Hunt M. P., 2004, *ApJ*, 604, 534
- Swinbank A. M., Smail I., Chapman S. C., Blain A. W., Ivison R. J., Keel W. C., 2004, *ApJ*, 617, 64
- Tacconi L. J. et al., 2013, *ApJ*, 768, 74
- Tremonti C. A. et al., 2004, *ApJ*, 613, 898
- Wolfire M. G., Hollenbach D., McKee C. F., 2010, *ApJ*, 716, 1191
- Yates R. M., Kauffmann G., 2014, *MNRAS*, 439, 3817
- Zahid H. J., Dima G. I., Kudritzki R.-P., Kewley L. J., Geller M. J., Hwang H. S., Silverman J. D., Kashino D., 2014, *ApJ*, 791, 130
- Zahid H. J. et al., 2014, *ApJ*, 792, 75

This paper has been typeset from a $\text{\TeX}/\text{\LaTeX}$ file prepared by the author.